

ESTIMATE

Cabrera Construction lic.
1135927
2752 Capistrano St
Antioch, CA 94509-4811

cabr_constr@yahoo.com
+1 (415) 359-5394
<https://cabrera.construction>



Bill to

jan hofwegen
241 hartford
street
sf, ca 94114 bay area

Estimate details

Estimate no.: 1059
Estimate date: 06/27/2026

#	Description	Rate	Amount
1.	PROJECT: REPAIR OF EXTERIOR MOLDINGS (TRIM) Quantity: 120 linear feet (ft) Scope: demolition, supply, installation, and painting 1. Cost Breakdown Demolition and Preparation: Removal of the rotten trim visible in the areas indicated in photos such as and inspection of the internal structure against moisture. Removal of debris. Global \$500 Materials (Premium): Treated outdoor wood suitable to resist moisture, galvanized nails, high elasticity sealant. \$1700 Labor (Installation): Cutting, adjustment and fixing of the new trim around the indicated windows and corners. \$1,800 Preparation and Painting: Caulking of joints, application of primer and two layers of premium exterior paint (in white to crush the current design). \$500	\$4,500.00	\$4,500.00
2.	PROJECT: RESTORATION, SANDING AND APPLICATION OF FINISHING ON EXTERIOR WOODEN BENCH 1. Scope of Work - Preparation of the Area: Removal and protection of objects on the bench (gas tanks, accessories) and protection of the terrace/patio floor against stains or residues. - Cleaning and Conditioning: Pre-washing of the wood to remove accumulation of mold, deep dirt and dead fibers caused by prolonged exposure to the sun and humidity.	\$2,050.00	\$2,050.00

- Deep Sanding: Complete sanding of the entire wooden surface (seats, integrated backs and side boxes) using orbital sanders and hand sanding in detailed corners to open the pore of the wood and remove the grayish/rusty layer.

- Application of Finish (UV Protection and Moisture):

- O Application of a layer of sealant/conditioner to ensure uniform absorption.

- O Application of two (2) layers of protective dye or high quality outdoor marine varnish (premium protection against UV rays and water).

2. Cost Estimate

The cost is based on the linear extension of the bench (square/L configuration with planters/side platforms) and the level of detail required for sanding between the wooden beams.

Description of the Concept Estimated Cost

Materials and Supplies (Sandper of different grains, wood cleaner, brushes/rollers, premium dye/outer protector) \$550

Specialized Labor (Preparation, washing, sanding in detail of the entire structure, application of two layers of finishing and final cleaning) \$1,500

ESTIMATED TOTAL:\$2050

3. Notes and Conditions

- Estimated Execution Time: 2 to 3 working days (depending on the drying time required between layers).

- Exclusions: Does not include replacement of rotten boards or major structural repairs on the bench support (will be evaluated if necessary at the time of sanding).

3.	Replacement of Handrails, Entrance Wood and Waterproofing	\$3,650.00	\$3,650.00
----	---	------------	------------

1. Scope of Work

- Demolition and Disassembly:

- O Removal and removal of the upper wooden handrail that is observed chipped and worn in the images.

- O Careful removal of the machi-fembrada wooden boards from the upper main entrance rest (area where the feet are shown in the photos) to expose the substructure.

- Waterproofing Sub-floor:

- O Cleaning and preparation of the structural base exposed under the rest.

- O Installation of a high-strength external grade waterproofing membrane (bituthene type or similar) to ensure that rainwater does not seep to the lower levels of the property.

- Carpentry and New Installation:

- O Installation of new treated wood for exteriors on the floor of the entrance rest, ensuring an airtight and level fit.

- O Supply and installation of a new wooden handrail with the appropriate outdoor profile, solidly attached to the existing blue structure.

- Finish: Sealing of joints with premium acrylic caulking and application of high durability paint / primer for exteriors in the intervened areas to match the existing colors.

2. Cost Estimate

Note: This estimate is calculated considering that the work requires structural carpentry and the handling of advanced waterproofing materials for weathering.

Description of the Concept Estimated Cost

Materials (Treated wood for floor and handrails, waterproofing membrane, galvanized structural screws, sealants and premium exterior paint) \$1050

Specialized Labor (Demolition of damaged areas, preparation and installation of waterproofing, carpentry of the handrail and entrance floor, painting and cleaning finishes) \$2,600

Total		\$10,200.00
-------	--	-------------

Accepted date 06/28/2026

Accepted by