

ESTIMATE

Cabrera Construction lic.
1135927
2752 Capistrano St
Antioch, CA 94509-4811

cabr_constr@yahoo.com
+1 (415) 359-5394
<https://cabrera.construction>



Bill to

AMANDA YEE
2583. 35 th avenue
san francisco ca, ca 94509

Estimate details

Estimate no.: 1035
Estimate date: 05/12/2026
Expiration date: 06/01/2026

#	Description	Rate	Amount
1.	Kitchen.	\$48,000.00	\$48,000.00

1. PROFESSIONAL SERVICES AND ADMINISTRATION

1. Structural Engineering: Design and calculations by an engineer for the removal of the wall (load verification).
2. Permit Management: Preparation and submission of plans to the San Francisco Department of Building Inspection (DBI) for demolition, plumbing, and electrical.
3. Inspections: Coordination of inspections required by the city during the process.

2. DEMOLITION AND STRUCTURAL PREPARATION

1. Demolition of the partition wall following the engineer's specifications.
2. Installation of beams or structural reinforcements if the design requires it.
3. Complete demolition of existing kitchen, air grille and legal disposal of debris.

3. RELOCATION OF SERVICES (MEP)

1. Plumbing: New configuration of water and drainage lines according to the new approved plan.
2. Electrical: Installation of 4 recessed LED lights, dedicated circuits for appliances and GFI outlets under current code.
3. Gas: Relocation of the supply line for the stove.

4. FINISHES AND CARPENTRY (MATERIAL AND WORKMANSHIP)

1. Cabinets: installation of high-quality cabinets with soft-close hardware.
2. Countertops: installation of Quartz or Granite
3. Repairs: Patching drywall (Smooth wall finish) and repairing the gaps in the wood floor to even out the existing area.
4. Painting: Preparation and complete painting of ceilings, walls, and trim. Only in areas. Working

SUMMARY OF ESTIMATED COSTS

Project Phase Estimated Total
Engineering, Drawings & Permitting Management \$5,000
Floor in some areas. , Structure & Repair \$8,000
Labor (Plumbing, Elect, Gas) \$8,500
Cabinets (Installation) \$15,000
Countertops (Installation) \$7,000

Drywall & Professional Painting \$4,500
PROJECT TOTAL (Estimated) \$48000

2.	Bathrooms	\$36,000.00	\$36,000.00
----	-----------	-------------	-------------

Architectural Design and Plans: Drawing of existing floor plan and new layout for city approval.

1. Permit Management: Procedures before the building department (city fees not included, usually paid by the client separately).

2. Estimated Cost Phase 1: \$5,500

2. Demolition y Preparation

1. Total removal of tiles, tub, pedestal and existing toilet.

2. Demolition of the floor for access to plumbing.

3. Demolition of walls necessary for the conversion of the closet into the second bathroom.

4. Removal of the existing window and structural patching of the exterior wall (Stucco/Siding).

5. Hauling of debris and containers (Dumpster).

Estimated 3. Construction Structural and Walls

1. Framing for the new doors (Pocket Doors).or regular door

2. Window gap closure and wall reinforcement for built-in cabinets.

3. Installation of "Backer board" (HardieBacker or Kerdi) in damp areas and moisture-resistant Drywall.

4. Tape, mud and texture.

5. Estimated Cost Phase 4: \$10500

4. Plumeria y Electricidal (Rough-in)

1. Plumbing: New configuration for two bathrooms. Installation of drainage system and water lines for 1 shower, 1 bathtub, 2 toilets and 2 sinks. Installation of mixing valves.

2. Electrical: Installation of new light boxes (as shown), exhaust fans (fans), and GFCI outlets as per code.

3. Estimated Cost Phase 3: \$8,000

5. Finishes and Installation (Labor)

1. Installation of tile on floors and walls (Shower and Tub area).

2. Waterproofing installation (waterproofing membrane).

3. Installation of the "Pocket Doors".

4. Mounting of built-in cabinets and vanities.

5. Installation of "Finish materials" (faucets, toilets, lights, mirrors, accessories).

6. Complete painting.

7. Estimated Cost Phase 5: \$12,000

Investment Summary (Labor and Basic Materials)

Concept Estimated Range

Plans and Permits (Management)

Demolition y Preparation \$ I would apply the same price for the bath and the kitchen.

\$5000

Construction Structural and Walls \$10,500

Plumbing & Electrical \$8,000

Finishes (Tile, Drywall, Installation) \$12,000

ESTIMATED TOTAL \$36,000

Important Customer Notes:

1. Finishing Materials (Provided by the client): Tiles, Grout, Tub, Sanitary Ware,

Vanities, Faucets, Lights, Doors and Hardware. counter top and gabinetes

2. Basic Materials (Included by the contractor): Wood (2x4), Drywall, Cement, Pipes (PEX/ABS), Electrical Wiring, Tile Glue, Waterproofing and Screws.

3. Estimated Time: 6 to 8 weeks once permits are obtained.

3.	New electrical subpanel installation.	\$1,000.00	\$1,000.00
----	---------------------------------------	------------	------------

Total	\$85,000.00
-------	-------------

Note to customer

Hello good. this. is. the. estimate. with the breakdown. of prices. if you. have. any questions. do not hesitate. to contact. the manager. of the company. Rafael. castro 5107305861. or. to the cabrera office. construction 4153595394 or. you. can. leave us an email. thank you.

Expiry date	06/01/2026
-------------	------------

Accepted date	05/13/2026	Accepted by
---------------	------------	-------------