

ESTIMATE

Cabrera Construction lic.
1135927
2752 Capistrano St
Antioch, CA 94509-4811

cabr_constr@yahoo.com
+1 (415) 359-5394
<https://cabrera.construction>



Bill to
ELIZABETH
534 shotwell st
san francisco, ca 94110
bay area

Estimate details

Estimate no.: 1038
Estimate date: 07/20/2026
Expiration date: 07/28/2026

#	Description	Rate	Amount
1.	1. PROJECT OVERVIEW The project consists of the preparation of the existing surfaces and the installation of a decorative Redwood wood cladding arranged horizontally on the perimeter walls of the roof. The aim is to cover the current walls to improve the aesthetic appearance of the terrace space, using slim 1-inch posts mechanically fixed to the base structure to minimize the loss of useful space. Surface Preparation and Cleaning 1. Deep cleaning: Removal of dirt, existing material. surface or vegetation accumulated on the perimeter walls before starting the installation 2. • Installation of battens/posts: Supply and fastening of 1-inch thick wooden posts to the existing perimeter wall. 3. • Structural fixing : Use of fittings and proper tight mechanical anchors. Wing the wall. Roof ensuring that the base is perfectly solid and level to receive the final finish. 4. All the material. It will be. Carried by the wall. Side up. By climbing it with the tools. Necessary to avoid damage and accidents. Installing Redwood 1. Coverage Dimensions: Total coverage of 65 linear feet by 5 feet tall (Approximate total area: 325 sq ft). 2. Horizontal installation: Supply and placement of high-quality 8x1cedar wood boards arranged horizontally on the support posts. 3. Precision Fits: Exact perimeter cuts to integrate with railings, corners, vents, and wall top trims 4. Installation of waterproofing of the new one. Wall. At the top and at each. Hole. What. It is had. What to do. When embedding screws Final Cleaning and Delivery 1. Collection and removal of all wood waste, dust and leftover materials generated during the working day. 2. Cleaning of the rooftop area (pavers and affected common areas) to leave the space completely walkable and clean.	\$8,000.00	\$8,000.00
2.	Installation of planters. The planters. They will be of. 18 inches. Wide by. 42 high. By 8 ft wide leaving a	\$1,300.00	\$1,300.00

space of 32 ft. In the center to. Install. A door between them. Code. Of the city
Including the base. Lined. From. Wood of the same material. From. 8x1. cedar
wood

3.	Demolition of jacuzzi. It would break. Small Stones And it would be transported. By. From the ceiling towards. The hallway. From the side. Of the building this would be. Completely free. By being. Working on the project	\$0.00	\$0.00
----	---	--------	--------

	Total	\$9,300.00
--	--------------	-------------------

Note to customer

This budget includes labor and material. Which one you want.
Question. Let. . Know.

Expiry date	07/28/2026
----------------	------------

Accepted date 07/20/2026

Accepted by